



**WASHTENAW COUNTY
FINANCE DEPARTMENT**

Purchasing Division

P.O. Box 8645, 220 N. Main, Ann Arbor, MI 48107-8645
Phone (734) 222-6760, Fax (734) 222-6764
www.purchasing.ewashtenaw.org

August 2, 2010

Addendum #1

RFP No. 6549

Title: Diesel Generator for Pittsfield Charter
Township

Due Date: Thursday, August 12, 2010 at 4:00PM

This addendum is generated due to various vendor questions.
Responses are attached.

Crystal A. Wake, CPPB, C.P.M.
Senior Buyer

cc: RFP 6549

QUESTIONS & ANSWERS

RFP #6549

Q1. Will owner accept alternate generator manufactures?

Yes. Alternate generators manufacture will be reviewed and considered after the bid opening. Alternate generator will be considered as long as specifications are met. Contractors will be required to submit a bid on the base generator and provide deduct/addition for any alternatives.

Q2. Will a full tank of fuel be required at the job completion?

Yes, in addition all fluids must be topped off for proper operations.

Q3. What kind of load bank test will be required?

At minimum an 80% full load test must be performed for a minimum of 2 hours, in addition the generator will power the building for one (1) hour after the load bank test.

Q4. What are the permit requirements?

Permit fees are not part of bid price. But, the contractor is responsible for obtaining all required permits. The owner will cover permit fees.

Q5. Who is responsible for the generator pad?

Generator pad will be installed by Pittsfield Township with an accessible trench underneath the pad to the "stub up area".

Q6. On Sheet E1.02 Note #15 calls for ¾" RGS w /10-#14 Generator Signals (Typ. Of 7), is this correct for 7 runs of conduits?

Only one (1) conduit is required with seven (7) pairs of generator signal wires.

Q7. Has the DEQ/MDNRe been consulted for this project? A remote fill may be required for the fuel. Located on the outside of the wall. Please advise.

The MDNRe has been contacted and the Owner will make the necessary modifications to meet the location requirements and also modification to the wall for the applicable requirements. A remote fill station will not be needed.